

To,

As per list enclosed

Sub: Invitation of sealed quotation for "Replacement of damaged insulation of air conditioning duct in NRTOL at Ground floor of Parivesh Bhawan, CPCB"

Sir,

Sealed quotations are invited on the behalf of Central Pollution Control Board for the following work: -

Scope of work: -

S.N	Description of items	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1.	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- Part I	60	Sqm		
2.	Dismantling roofing including ridges, hips, valleys and gutters etc. and stacking the material within 50 metres lead of: G.S. Sheet	60	sqm		
3.	Supplying and fixing of following thickness duly laminated aluminum foil of mat finish closed cell Nitrile rubber (Class "O") insulation on existing duct after applying suitable adhesive for Nitrile rubber . The joints shall be sealed with 50 mm wide and 3 mm thick self adhesive nitrile rubber tape insulation complete as per specifications and as required. 19mm	100	sqm		
	Total				
	Taxes, if any				
	Grand total				

Terms & Conditions:

1. Sealed quotations should be dropped in the quotation box kept at reception (Ground Floor) of Parivesh Bhawan, CPCB on or before 20.06.2019 by 11.00 a.m.
2. The quotation has to be accompanied by an EMD of Rs. 2757/- (Rs. Two Thousand Seven Hundred Fifty Seven only) as Demand Draft in favour of Central Pollution Control Board, Delhi. The EMD of unsuccessful bidders shall be returned after award of work to successful bidder. The EMD of successful bidder shall be deposited in CPCB account and will be refunded after defect liability period of 06 months. No interest shall be paid on it.
3. The bidders should have registered contractor of CPWD /other Govt. organisation or dealer/service centre of VRF air conditioning system.
4. The bidder has to submit copy of valid copy of PAN Card, GST registration and copy of registration with CPWD or any other Govt. organisation or documentary evidence of dealer/service centre of VRF air conditioning system alongwith the bid.
5. Payment will be made after satisfactory completion of work after submission of bill alongwith copy of the GST challen deposited for this work. No advance payment will be made.
6. 10% security will be deducted/retained from the bill for defect liability period of 06 months.
7. The defect if any, found within 06 months after completion of the work should be rectified by the quotee at his own cost.
8. The work should be completed within one month from the date of issue of work order.
9. Income Tax shall be deducted at source.
10. The work shall be carried out strictly according to CPWD specifications for electrical work.
11. It may be noted that mere quoting the lowest rates will not entitle any firm to get the work order.
12. The Chairman, Central Pollution Control Board reserves the right to cancel any or all the quotations without assigning any reasons thereof.
13. The quotations shall be valid for 01 months from the date of their opening.
14. The terms & conditions and taxes etc. should be clearly mentioned in the quotation.
15. The over writing and corrections, if any should be counter signed.
16. In the event of any dispute, the decision of the Chairman, Central Board shall be final and binding on both the parties.
16. Typographical & clerical errors are subject to correction.

Yours Faithfully,

(D. Gouda)
Div. Head, Building Div.

Copy to : I/c, F&A, CPCB